		0	1
Agenda Item	Number	O	)

# Memo

To: Village Board

Fr: Trevor Fuller, Planning and Zoning Administrator

Re: APPROVAL SITE PLAN AND DESIGN REVIEW OF GREEN BAY AREA PUBLIC SCHOOL DISTRICT DOTY ELEMENTARY AT 525 LONGVIEW AVENUE

Date: 22 February 2018

Attached are the proposed plans submitted by the Green Bay Area Public Schools (GBAPS) for the site plan and design review of the proposed entrance addition to Doty Elementary School at 525 Longview Avenue (see attachment 1). A representative will be present at the meeting to talk about the project and answer any questions.

## Site Plan and Design Review Process

The site plan and design review process is an opportunity for the Village Board and the plan commission members to review and to ensure the plans meet village standards in regards to safety, efficiency, aesthetics, and legal concerns in a public forum. The village cannot consider the use of the parcel as part of the decision in this process, only review if the proposed development meets all site plan and design standards for this zoning district.


The proposed project is for parcel AL-1385-1, located at 525 Longview Avenue. This parcel is zoned "A' Residential" and the proposed use is allowed under this zoning classification. The plan commission is asked to review the Doty Elementary addition proposal and determine if the proposed project meets the zoning and design requirements required by the zoning code for this proposed use.

## Staff Comments and Recommendation

Staff has reviewed the proposed plans and has provided GBAPS with comments (see attachment 2).

Staff recommends the plan commission recommend approval of the petition by the Village Board, should all comments be addressed and necessary permits be filed prior to a final building permit being issued or a reasonable explanation (as determined by staff and the Village Board) as to why these comments were not addressed.

Plan commission is asked to recommend or not to recommend approval of the petition from GBAPS, requesting a site plan and design review for a development on parcel AL-1385-1, located at 525 Longview Avenue.



SITE PLAN 1.0 SCALE: I" = 30'

I ONGVIEW AVENILIE

# SHEET KEY NOTES:

- 1 INLET PROTECTION; SEE DETAIL A SHEET C2
- (2) ALL EXCAVATION SHALL BE FROM PAVED SURFACE. IF EXCAVATION IS TO OCCUR OUTSIDE PAVED AREAS, CONTRACTOR SHALL PROVIDE A STONE TACKING PAD PER DETAIL B SHEET C2
- 3 LIMITS OF DISTURBANCE = 5,905 SF

# **EROSION AND SEDIMENT** CONTROL PLAN STATEMENT:

THE SITE IS LOCATED ON PARCEL AL-1385-1 (525 LONGVIEW AVENUE). EXISTING IMPROVEMENTS ON SITE CONSIST OF DOTY ELEMENTARY SCHOOL, DRIVES AND IMPROVEMENTS OF STEEL ST DEMOLITION, EXCAVATION, BACKFILL AND PAVING, RUNOFF FROM THE PROJECT AREA WILL DISCHARGE TO EXISTING CATCH BASINS LOCATED ON SITE.

EROSION CONTROL BMP'S TO BE IMPLEMENTED INCLUDE INLET PROTECTION. ANY DISTURBED LANDSCAPING WILL BE RE-VEGETATED.

LAND DISTURBANCE IS ESTIMATED TO BE 0.11 ACRES.

ESTIMATED CONSTRUCTION SCHEDULE IS MAY 2018 TO AUGUST 2018

# CONSTRUCTION SEQUENCE:

- MAY 2018 AUGUST 2018

   INSTALL EROSION CONTROL DEVICES IN ACCORDANCE WITH THE WDNR
- TECHNICAL STANDARDS AND STORMWATER MANAGEMENT PLAN.
   CONSTRUCT BUILDING
- INSTALL BASE COURSE
- INSTALL PAVEMENT
- REMOVE EROSION CONTROL BMPS UPON SITE STABILIZATION

### PLANNED EROSION CONTROL PRACTICES:

- INLET PROTECTION (TECH STANDARD 1060)
   INLET PROTECTION SHALL BE INSTALLED AT ALL EXISTING AND PROPOSED STORM DRAIN INLETS ON THE PROJECT SITE AND IMMEDIATELY DOWN STREAM FROM ANY DISTURBED AREAS.
   DUST CONTROL, CTECH STANDARD 1068)
   DUST CONTROL SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE ABOVE MENTIONED TECHNICAL STANDARD. WHERE POSSIBLE DUST CONTROL SHALL BE WISDOT TYPE B SOIL STABILIZER OR TEMPORARY SEED.

  3. TEMPORARY CONSTRUCTION ENTRANCE/EXIT (TECH. STANDARD 1057)
   A NEW GRAVEL CONSTRUCTION ENTRANCE WILL BE INSTALLED AT ALL CONSTRUCTION ACCESS POINTS TO PREVENT SEDIMENT FROM TRACKING ONTO THE ROADWAYS.

  4. DEWATERING TECH STANDARD 1061
- 4. DEWATERING (TECH STANDARD 1081)
  SHOULD DEWATERING BE REQUIRED FOR INSTALLATION OF PLANNED IMPROVEMENTS, SEDIMENT SHALL
  BE REMOVED FROM WATER GENERATED DURING DEWATERING ACTIVITIES PRIOR TO DISCHARGING OFF-SITE OR TO WATERS OF THE STATE.

#### MAINTENANCE PLAN:

- 1. ALL EROSION CONTROL AND STORM WATER MANAGEMENT PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION EVERY 7 DAYS AND WITHIN 24 HOURS OF A STORM PRODUCING AT LEAST 0.5 INCHES OF RAINFALL. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED. ALSO, ANY SEDIMENT THAT HAS BEEN DEPOSITED OFF-SITE FROM THIS CONSTRUCTION PROJECT SHALL BE CLEANED UP IMMEDIATELY.

  2. COPIES OF THE EROSION & SEDIMENT CONTROL PLAN SHALL BE KEPT ON SITE.

  3. MAINTAIN EROSION AND SEDIMENT CONTROL PER THE PLAN AND AS NECESSARY TO MEET THE REQUIREMENTS OF THE ORDINANCE, UNTIL THE SITE HAS UNDERGONE FINAL STABILIZATION AND RECEIVED FINAL ACCEPTANCE FROM THE MUNICIPALITY.

  4. AN EROSION AND SEDIMENT CONTROL PRACTICE INSPECTION LOG SHALL BE MAINTAINED. LOG SHALL NOTE THE TIME, DATE AND LOCATION OF INSPECTION, THE PHASE OF CONSTRUCTION AT THE SITE, PERSON DOING THE INSPECTION, ASSESSMENT OF CONTROL PRACTICES, AND DESCRIPTION OF EROSION AND SEDIMENT CONTROL MEASURES OF MAINTENANCE DONE IN RESPONSE TO INSPECTION.

### CONSTRUCTION NOTES:

- 1 FROSION CONTROL METHODS SHALL BE IMPLEMENTED AS DIRECTED BY THE ENGINEER PRIOR TO AND EROSION CONTROL METHODS SHALL BE IMPLEMENTED, AS DIRECTED BY THE ENGINEER, PRIOR TO AND DURING CONSTRUCTION, TO CONTROL WATER POLLUTION, EROSION AND SILTATION, INCLUDING, BUT NOT LIMITED TO HAY BALE DIKES AND SILT FENCES. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE WIDNE TECHNICAL STANDARDS. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS. CONTRACTOR IS RESPONSIBLE FOR CONTACTING DIGGERS HOTLINE FOR THE LOCATION OF THE UTILITIES.
  SITE DEWATERING IS NOT ANTICIPATED, HOWEVER SHOULD DEWATERING BE NECESSARY, IT SHALL BE PERFORMED IN ACCORDANCE WITH WDNR TECHNICAL STANDARD (1061).
  THE CONTRACTOR SHALL DISPOSE OF ALL WASTE AND EXCESS MATERIAL AT AN APPROVED LOCATION.

# NOTE

ELEVATIONS ARE ON BROWN COUNTY DATUM.






ELEMENTARY SCHOOL
I BAY AREA PUBLIC SCHOOLS
I BAY, WISCONSIN DOTY E GREEN GREEN

PLAN DOTY SCHOOL EROSION CONTROL



(?) FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2" X 2". THE REBAR, STEEL PIPE OR WOOD SHALL BE INSTALLED IN THE REAR FLAP AND SHALL NOT BLOCK THE TOP HALF OF THE CURB FACE OPENING.

# **INLET PROTECTION**



ELEMENTARY SCHOOL

I BAY AREA PUBLIC SCHOOLS

I BAY, WISCONSIN DOTY E GREEN GREEN

PLAN DOTY SCHOOL EROSION CONTROL



# Site Plan & Design Review - Staff Comments

Site:

525 Longview Avenue (Parcel AL-1385-1)

**Development:** 

Green Bay Area Public Schools (GBAPS) - Doty Elementary School

**Developer Representatives:** 

GBAPS – Michael Strangel – Executive Director of Facilities and Related Services

Architects Group Limited - Carl Winnekins - Project Architect

Zoning Department review:

Zoning district Building use (allowed)		"A" Residential			
		Schools which are public or church-affiliated educational institutions			
		Required	Provided	Notes	
Height		Lesser of 35' or 2½ stories	Not provided	Font elevations and building heights not provided. Should be discussed at the meeting.	
Lot	Area	7,500SF minimum	Standards met		
	Frontage	100'minimum	Standards met		
	Green space	N/A for public and semipublic buildings, such as churches, schools and hospitals	N/A		
Setback Front Side (inner) Side (corner) Rear	Front	30'	Existing		
	Side (inner)	10'	Existing		
	Side (corner)	N/A	N/A		
	30'	Existing			
Parking Number  Size  Bicycle	Number	Elementary, middle or junior high school (1 stall / 5 seats provided in the main assembly rooms)	53		
	Size	10'x20'	Existing		
	Bicycle	Bicycle parking should be provided	Standards met		
Access	Automobile	24' drive lanes with 90 degree parking	Existing		
	Pedestrian	ADA compliant sidewalks	Standards met		
Architecture		Varied rooflines and other architectural designs that break-up the building mass	Not provided	Font elevations not provided. Should be discussed at the meeting.	
Exterior finishes		Brick, stone, glass, fiber cement siding, EFIS, stucco, wood siding	Not provided	Font elevations and exterior finishes not provided. Should be discussed at the meeting.	
Lighting		Dark sky compliant, no light directed towards ROW, no more than 0.2FC at property line, must be shut off at 10p.m.	Standards met		
Sign		N/A	N/A		
Fences/So	creening	N/A	N/A		

<sup>\*\*</sup>All other zoning requirements for "A" Residential District stipulated in Chapter 475 of Village Ordinances should be met to the highest degree possible.

- Fire Department review:
  - Standards met.
- Parks, Recreation, and Forestry Department review:
  - No comment.
- Public Works Department review:
  - All stormwater and erosion control requirements shall be met.

# Additional comments:

 Construction access – traffic on Longview Avenue shall not be obstructed during construction. Dirt and debris shall be kept on-site and off of the public roadway.

Date Reviewed:

February 22, 2018

**Comments Submitted By:** 

Trevor Fuller, Village of Allouez Planning & Zoning Administrator